

15-051-05109-0000

Form CP-3  
Rev. 6-26-62

KANSAS

*10*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Ormand Industries, Inc.

Complete Address: 2118 Adolphus Tower Dallas, Texas 75202

Lease Name Bemis "A" Well No. 8

Location SW NE NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3500

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:15A Day 3 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 3500' 10 3/4 csg set at 1120' cwc 600 sk.

7" csg set at 3479' cw 300 sk cmt.

Filled 7" csg W/sd (3460-3500) Dumped 7 sk cmt W/dump bailer. (3420-3460)

Cutoff and recovered 1423' of 7" csg.

Pumped thru 10 3/4 plg cont. with 30 sk gel W/5 sk hulls, plug and 155 sk 50-50 poz cmt.

W/6% total gel. Max. pres. 650 lbs. SI pres. 350 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: *[Signature]*  
Well Plugging Supervisor

INVOICED  
DATE 5/6/69  
INVOICE NO. 9721-4