

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.

Complete Address 12011 San Vicente Blvd., Los Angeles, California 90049

Lease Name Bemis "A" Well No. 6

Location SE NE NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3457'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10:30 A Day 13 Month 7 Year 1973

The above well was plugged as follows:

Total Depth 3457' 15 1/2 csg set at 34' cwc 25 sk. 10 3/4 csg set at 1157' cwc 225 sk.

7" csg set at 3450' cw 125 sk cem.

Tools lost in hole at A/2200'.

Set wood plug at 2200'--poured 30' sand--dumped 5 sk cmt W/dump bailer. (2150-2200)

Cutoff and removed 1451' of 7" csg.

Filled 10 3/4 csg with mud to 420' --set rock & sand bridge (400-420)

Dumped 8 yds readymix cmt from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Manning
Well Plugging Supervisor

7/18/73
7649-W