

15-051-03358-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Oramand Industries, Inc.

Complete Address: 2118 Adolphus Tower Dallas, Texas 75202

Lease Name Bemis "A" Well No. 6 (New)

Location SE ~~NE~~ NW Sec. 22 Twp. 11 Rge. 17 (E) (W) X

County Ellis Total Depth 3489

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:15A Day 25 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 3489' 8 5/8 csg set at 996' cwc

5 1/2 csg set at 3489' cw 150 sk cmt.

5 1/2 csg PBD 3478' Perf. (3446-3440)

Filled 5 1/2 csg W/sd (3425-3478') Dumped 5 sk cmt. W/dump bailer(3385-3425)

Shutoff and recovered 2089' of 5 1/2" csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls and 120 sk 50-50 poz cmt W/6% total

gel. Max pres. 400 lbs. SI pres 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

4/28/69
9653-4