

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ormand Industries, Inc.

Complete Address: 2118 Adolphus Tower, Dallas, Texas 75202

Lease Name Bemis A. ~~DWP rec~~ Well No. 5

Location NE NE NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3439

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 1:15P Day 3 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 3439' 15 1/2" csg at 30' cwc 30 sk 10 3/4" csg at 1137' cwc 325 sk.

7" csg set at 3430' cw 125 sk cmt. 4 1/2" liner set (2195-3425)

Filled 4 1/2" liner W/sd (3400-3439) Dumped 4 sk cmt W/dump bailer. (3360-3400)

Shutoff and recovered 1620' of 7" csg.

Pumped down 10 3/4" csg with 30 sk gel W/5 sk hulls and 155 sk 50-50 poz cmt W/6% total gel.

Max. pres. 550 lbs. SI pres. 350 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: R. J. Massey
Well Plugging Supervisor

INDEXED
DATE 5/6/69
ENV. NO. 9720-W