

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ormand Industries, Inc.

Complete Address: 2118 Adolphus Tower, Dallas, Texas

Lease Name Bemis "A" Well No. 4

Location NW NE NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3460'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5:45P Day 3 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 3460' 15" csg set at 34' cwc 25 sk. 10 3/4 csg set at 1127' cwc 325 sk.

5" liner set (2470-3460) cemented.

7" csg set at 3424' cw 125 sk cmt.

Filled 5" liner W/sd (3400-3460) Dumped 5 sk cmt W/dump bailer. (3360-3400)

Shutoff and recovered 1570' of 7" csg.

Pumped down 10 3/4 csg with 30 sk gel W/5 sk hulls and 155 sk 50-50 poz cmt W/6% total gel.

Max. pres. 650 lbs. SI pres. 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

RECEIVED
MAY 6 1969
9219-W