

15-051-05846-0001

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1973
04-27-73
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.
Complete Address 12011 San Vicente Blvd. Los Angeles, California 90049
Lease Name Bemis "A" Well No. 2
Location SW NW NW Sec. 22 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3400'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 10 A Day 24 Month 4 Year 1973

The above well was plugged as follows:

Total Depth 3400' 15 1/2' csg at 108' cw 25 sk. 10" csg at 1095' cwc 325 sk.

7" csg set at 3396' cw 150 sk cmt.

5" liner cmt'd (3360-3457) & perf. (3421-3427)

Set 5 1/2" plug at 3360' -poured 10" sand -dumped 6 sk cmt W/dump bailer.

Cutoff and recovered 1687' of 7" csg.

Set 10" wood plug at 375' -rock & sand (365-375)

Dumped 7 yds readymix cement from 365' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

Signed: Geo. L. Wassen
Well Plugging Supervisor

DATE 4/30/73
INV. NO. 7296-W