

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 140-41  
LOCATION SE-SW-SW  
SEC. 22 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 8 Lease Bemis  
Operator Russell Supply Co Address Russell, Kans.  
Field \_\_\_\_\_ County Ellis

Total Depth 3432 Feet.

Plugging Contractor Arnett Casing Pulling Co.

Plugging Contractor's License No. 265

Address Hoisington, Kansas.  
(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 1163' c.w.c. 7" o.d. set 3424'  
w/ 175 sv Cem. Plugged back to 2870' top perf  
2850'. Hole mudded and sanded to 2500'  
dumped 5 sv Cem. Shot off and pulled 7"  
Casing. Filled hole with mud to 300' set  
rock bridge and run 25 sv Cem. Mud to  
35' rock bridge and 10 sv Cem. to base of cellar.

Warren S. Horner  
District Conservation Agent

Date Aug 18, 1955

08-22-55

**PLUGGING**  
FILE 08-22-11-217W  
BOOK PAGE 140 LINE 41