

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 51-7

LOCATION NE SW SW

SEC. 22 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 7 Lease FA Bemis DUB KC

Operator British - American Oil Address Box 91 Hoisington, Kans

Field Bemis County Ellis

Total Depth 3589 Feet.

(Describe briefly the manner in which the well was plugged)

15 1/2" at 142' circulated with cement- 10 3/4" at 1208' circulated  
with cement, 7" at 3471' with 170 sax behind - 4 1/2" at 3589' with  
60 sax behind - Cemented back to 3497' - top perforations at  
3471' - Filled hole with chat to 3455' set 7 sax cement with dump  
bailer, pulled 3458' 4 1/2" casing and 2600' 7" casing, filled hole  
with heavy mud to 250', set rock bridge and 20 sax cement, filled  
with heavy mud to 30', set rock bridge and 10 sax cement to botto m  
cellar.

**PLUGGING**  
 FILE SEC 204 11 R 176  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

01-22-51

[Signature]  
 District Conservation Agent

Date 1-16-51