

15-051-03363-0090

DISTRICT CONSERVATION AGENT'S REPORT

(Handwritten scribble)

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 147-9

LOCATION NW SW SW

SEC. 22 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 5 Lease F.A. Remis DWB rcc

Operator Toland & Reeves Address c/o Forbes Casing Pulling Co
Great Bend, Kans

Field _____ County Ellis

Total Depth 3420 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

10 5/4" at 1140' circulated with 437 sax cement - 10" at 193'

circulated with cement - 7" 3421' with 175 sax cement behind.

Filled with sand to 3410', set 5 sax cement with dump baller,

pulled 1030' 7" - filled hole with heavy mud to 500', set rock and

30 sax cement, heavy mud to 35', set rock and 15 sax cement to

bottom cellar.

(Signature)
District Conservation Agent

Date 5-10-57

PLUGGED
SEC. 22 T. 11 R. 17W
BOOK PAGE 147 LINE 9

05-28-57