

15-051-05847-00-01

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.

Complete Address 12011 San Vincente Blvd., Los Angeles, California 90049

Lease Name Bemis "B" Well No. 1 (SWD)

Location NW SW NW Sec. 22 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3914'

Abandoned Oil Well Gas Well Input Well SWD Well XXX D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas License No. 683

Operation Completed: Hour 1:30 P Day 13 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 3914' 15 1/2" csg 110' cwc 100 sk 12 1/2" csg 1078' cwc 325 sk.

7" csg set at 3355' cw 125 sk.

5 1/2" csg set at 3355-3400 & cemented.

4 1/2" csg set at 3322-3646 cemented. No pipe recovered.

Washed tbg down 7" csg to 287'. Pumped 8 sk gel & water & 500 lbs hulls -displaced 150 sk poz cement 6%.

Pulled tbg to 155' & circulated 75 sk poz 6% to base of cellar. Pulled tbg & capped 7" csg with cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Boo F. Murrey
Well Plugging Supervisor

INVOICED
DATE 6/15/73
INV. NO. 7509-U