

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-23,091-00-00 *✓ R*

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Green Oil Operations

Complete Address Box 503, Hays, Ks. 67601

Lease Name Unrein Well No. 1

Location 100' N. SE NE SE Sec. 14 Twp. 13 Rge. 18 (East) (West)

County Ellis Total Depth 3325'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A XXX

Other well as hereinafter indicated     

Plugging Contractor Big Springs Drilling, Inc.

Address Box 8287 Munger Sta. 400N. Woodlaun, Wichita, Ks. License No. 67208

Operation Completed: Hour: 1:00 AM Day: 27 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All      Part      None XXX

The above well was plugged as follows:

8 5/8"-250' S.P. cuc. w/165 sacks common-2% Gel.-3% Cal.Cl.

Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 660' w/80 sacks cement

2nd plug @ 260' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 250' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: *[Signature]*  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

      
      
    

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 02 1982  
CONSERVATION DIVISION  
Wichita, Kansas  
8-9-82  
799-W

Signed:       
Conservation Division Agent

*[Signature]*