

KANSAS

Form CP-3
Rev. 6-4-68

f

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051- 21,591-00-00 (of this well)

Operator's Full Name Graham-Michaelis Corp.

Complete Address Box 247, Wichita, Kansas

Lease Name Pfeifer Well No. 1-14

Location 1540' FSL & 1695' FWL of SW/4 110'S & 45' E S10 N2 S10 Sec. 14 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3760'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 5:45 P Day 22 Month 11 Year 1978

The above well was plugged as follows:

RTD 3760' 8 5/8 csg set 653' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1978

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-29-78
INV. NO. 8614-W

Signed: Leo Massey
Well Plugging Supervisor