

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
FORM CP-3
Rev. 1-8-82
OCT 07 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-051-23, 170-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name DREILING RESOURCES, INC H/c #534
Complete Address ROUTE I BOX 278 VICTORIA, KANS. 67671
Lease Name POLIFMA Well No. #1
Location NE-NE-SE Sec. 17 Twp. 13 Rge. 18 (East)(West)
County ELLIS Total Depth 3710 FT.
Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated
Plugging Contractor DREILING OIL INC (H/c #534)
Address RI VICTORIA, KANS. 67671 License No.
Operation Completed: Hour: 6:00 PM Day: 23RD Month: SEPT Year: 1982
Plugging Operations attended by Agent?: All Part None X

The above well was plugged as follows:

8 5/8" - 161 FT SP. CUL. w/ 125ST QUICK SET. (BY SUN CMT)
ORDERED 120ST 50/50 Pozmix 4% GEL-3% CM-CL AND 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST Plug @ 720 FT w/ 80ST CMT.
2ND Plug @ 240 FT w/ 40ST CMT.
3RD Plug - SOLID BRIDGE HULL'S - Plug. @ 40 FT w/ 10ST CMT.
10ST IN RAT HOLE. (CIRCULATE)
10ST IN MOUSE HOLE. (CIRCULATE)

Amount of Surface Casing: 161 FT

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Marian Schmidt
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

10-18-82
1389-u