

5-25-88

384 R

To: 1 040105
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15,007-21,748 0000

SE SE NE, SEC. 17, T 31 S, R 10 W
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8653

Lease Name Carter Well # 17-1

Operator: Petroleum Technologies, Inc.
Name & Address 3535 Broadway, Suite 200
Kansas City, MO 64111

County Barber 148.20
Well Total Depth 4560 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 25 Month: 5 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3866' PBDT 3866' Perfs at 3701-05'

1st plug pump 2 sx hulls, and 30 sx cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 a.m. Day: 25 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 100 lbs. of hulls, and 30 sx common cement, stop plug at 3500',

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 800 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2800' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 6-22-88
INV. NO. 20935

Signed Stephen J. Pfeiffer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN - 2 1988
CONSERVATION DIVISION
Wichita, Kansas