

To: 1 040726 12-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,791 - 00-01 940  
SW NW SW, SEC. 24, T 34 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9459  
Operator: C.E. Kimmell  
Name & Address: 1716 Milam Building  
San Antonio, TX 78205

1787 feet from S section line  
4813 feet from E section line

Lease Name R.V. Nelson Well # 1  
County Barber

Well Total Depth 5360 174.20 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hardtner Well Service License Number 5255

Address \_\_\_\_\_

Company to plug at: Hour: 12 p.m. Day: 21 Month: 12 Year: 19 92

Plugging proposal received from Keith Shahan

(company name) Hardtner Well Service (phone) \_\_\_\_\_

work: 4 1/2" at 5368' w/500 sx cement, Perfs at 4653-80, BP 4134', Perfs at 3948-52'  
1st plug sand back to 3900' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 100 sx cement.

RECEIVED  
COMMISSION  
DEC 30 1992  
Steve Pfeifer  
CONSERVATION DIVISION  
(TECHNICIAN)

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 p.m. Day: 21 Month: 12 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2945' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 1-14-93

INV. NO. 37194

12-21 FEB 24 1993

Signed Stephen J Pfeifer (TECHNICIAN)