

4-100533

Received
07-15-1998

6-8

TO:

API number: 15-051-24,983-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

NW NE NE SEC: 06, 13, 19 W
330 Feet from N (N/S) Line
990 Feet from E (E/W) Line

Operator License# 31980

LEASE: Slaughter WELL # 1

Operator: Lotus Operating Company, LLC

County: ELLIS 126.75

Address: 107 N. Market
Suite 416
Wichita, Ks 67202

Well total Dept 3900 feet
Conductor Pipe inch @ feet
Surface pipe 8 5/8 inch @ 226 feet

Aband. Oil Well Gas Well Input Well SWD: D & A: X

Plugging contractor: Shields Drilling License#: 05184

Address: Russell, Ks

Company to plug at: Hour: ? Day: Month: Year:

Plugging proposal received from Burt Beery

Company: Shiels Drilling Phone:

Were:

- 1st plug @ 3850' with 25 sx
- 2nd plug @ 1500' with 25 sx
- 3rd plug @ 760 with 100 sx
- 4th plug @ 270' with 40 sx
- 5th plug @ 40' with wiper plug and 10 sx

Plugging proposal received by: David Wann

Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 2:45 PM Day: 8 Month: June Year: 1998

Actual plugging report:

Hole plugged as above.
Order 225 sacks of 60/40 Posmix w/6% gel and 1/4 lb flowcell per sack.

Remarks: Elevation: 2162 GL, Anhydrite top: 1501 feet Anhy. plug: Y

Dakota plug: Y Bottom plug in place Y

Plugged through drill pipe Y

Arbuckle top 3850 Cemented by: Allied Cementing

I did [] did NOT [X] observe the plugging.

David Wann
David Wann
(agent)

P.I.R.T. III

INVOICED

DATE 6-18-98

INV. NO. 50778