

2030160

15-015-4092/20000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- April-27-1947

NW SW SE, SEC. 18, T 25 S, R 5 E

990 feet from NS section line

2310 feet from SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Robison Well # 18

Operator: Gear Petroleum Co. Inc.

County Butler 83.75

Name & Address 300 Sutton Place Bldg.

Well Total Depth 2577 feet

209 E William

Conductor Pipe: Size _____ feet

Wichita, Kas. 67202

~~Surface~~ Casing: Size 7" feet 2540

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Phillips Well Service License Number 5870

Address Box 1263, Eldorado, Kas. 67042

Company to plug at: Hour: 8:30 A.M. Day: 4 Month: 12 Year: 19 84

Plugging proposal received from Buck Faulkner

(company name) Gear Petroleum Co. Inc. (phone) 316-321-3653

were: (15 1/2" cas. 195' - 12 1/2" cas. 925' - 10" cas. 1680' - 8 3/4" - 2165' - all pulled)

run tub inside 7" cas as far as possible, spot 50% cement, pull tub.

run S.M. to ck top of cement, run tub outside 7" cas. to 250', pump

cement to surface, pull tub, run tub inside 7" cas. to 250' pump

cement to sur.

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 P.M. Day: 4 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT Ran 2 3/8" tub to 2555' United Cementing # 6744

spotted 50% cement, pulled tub, ran S.M. to top of cement. 2321', ran

tub outside 7" cas to 250', pumped 50% gel, 200 lbs, 150% cement, pulled

tub, let set. Ran tub outside 7" cas to 180', pumped 400% cement to surface

pulled tub, ran tub inside 7" cas to 250', pumped 90% cement

to surface. pulled tub.

Remarks: all cement was 60-40 Premier 4% gel, 3% cc, 1/4" floual, 2 1/2" ball.

(If additional description is necessary, use BACK of this form.)

I (did) did, not) observe this plugging 12-19-84

6036

12-12-84
DEC 12 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed Don Thompson
(TECHNICIAN)