

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-13

API NUMBER 15- 067-20,841 0000
C NW SE, SEC. 19, T 28 S, R 36 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA INC.
Name & Address: P.O. Box 26100
Oklahoma City, OK 73126-0100

Lease Name Spikes Well # A-4
County Grant 189.38
Well Total Depth 5827 feet
Conductor Pipe: Size 20 feet 48
Surface Casing: Size 8 5/8 feet 1796

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor OXY USA INC. License Number 5447
Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 9 a.m. Day: 13 Month: 7 Year: 19 95

Plugging proposal received from Harold Jones
(company name) OXY (phone) 316-356-3032

work: 5 1/2" at 5826' w/ 625 sx cement, DV tool at 3083' w/880 sx cement,
1st plug set CIBP at 5200' with 2 sx cement on top, run tubing and load hole with mud,
2nd plug pump 50 sx cement at 3008',
3rd plug pump 30 sx cement at 1823',
4th plug pull tubing to 598' and circulate cement to surface with 70 sx.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 13 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5200' with 2 sx cement on top,
Ran tubing in and loaded hole with mud:
2nd plug pumped 50 sx cement at 3008',
3rd plug pumped 30 sx cement at 1823',
4th plug pulled tubing to 598' and circulated cement to surface with 70 sx.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.
DATE 7-28-95
INV. NO. 43189
7-13

Signed Glenn R. Barlow (TECHNICIAN)
07-20-95