

6 010294

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-24127-000  
NW, SEC. 17, T. 13 S, R. 19 (W) E  
2970 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5562  
Operator: Liberty Oper. & Comp.  
Name & Address 308 W. Mill  
Plainville KS.

Lease Name Bemis Well # 1  
County Ellis 123.99  
Well Total Depth 3815 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 517 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pioneer Drilg License Number 5665  
Address Same

Company to plug at: Hour: 10 PM Day: 14 Month: 2 Year: 19 85

Plugging proposal received from Tom Alm

(company name) Pioneer Drilg (phone) \_\_\_\_\_

were: order 170 5x. cem. 50/50 formix. 6% gel 30% c.c.  
Heavy mud between all plugs.  
Pump cem. down drill pipe.

Elev- 2070 Anhydrite 1417-55 Arbuckle. 3769

Dakota. 1700 Plugging Proposal Received by Delif Batthozor  
370 = 670 (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None ✓

Operations Completed: Hour: 5:30 AM Day: 15 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT circ. @ 3770 for 45 mi STATE CORPORATION COMMISSION

25 5x @ 3770  
25 5x @ 1440  
100 5x @ 670 w/ 15x flow seal  
10 5x @ 40 on Solid Bridge.  
10 5x in Rat Hole

Remarks: cem. Co. Allied  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 2-26-85

NV. NO. 7140

Signed Delif Batthozor 13  
(TECHNICIAN) 2-22-85