

2030162

15-015-4090-0000  
API NUMBER 15-10-2-1946

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SE, SEC. 18, T 25 S, R 5 E

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Robison Well # 17

Operator: Gear Petroleum Co. Inc.

County Butler

Name & Address 300 Sutton Plaza Bldg.

Well Total Depth 2587' 84.08 feet

209 E. William

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita, Ks. 67202

Casing: Size 5 1/2" feet 2508'  
3" feet 2415' extmp.

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Phillips Well Service License Number 5870

Address Box 1263, Eldorado, Ks. 67042

Company to plug at: Hour: 3:00 P.M Day: 5 Month: 12 Year: 19 84

Plugging proposal received from Buck Faulkner

(company name) Gear Pet. Co. Inc. (phone) 316-321-3653

were: (15 1/2" cas. 170' - 12 1/2" cas. 865' - 10 3/4" cas. 1650' - 8 7/8" cas. 2165' - all pulled)

6-1951 squeezed hole in 5 1/2" cas. 153' / 200 ex cent. - 4-19-7971 - squeezed

bottom of 3" with 33 ex cent. Pump hose 1000' S.I.P. 1200' did not drill out.

try to pull 3", pump perf. 5 1/2" 250', pump cent. to surface

Plugging Proposal Received by Don Thompson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 8:30 AM Day: 6 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT Shot & pulled 266' of 3". perf. 5 1/2" cas. 250' 4-holes

ran 2 3/8" tub to 250. United Cementing # 6604, pumped 300 ex

cent. pulled tub, let set. 7:30 A.M 12-6-84, ran tub to 35' (top cent)

pumped 10 ex cent. to surface, pulled tub, ran tub to 35'

1 joint pumped 50 ex cent. to surface

Remarks: All cement was 60/40 pas. 4% gel 3% cc. 1/4" fluvial 2% hells. 2 3/8" cas in hole

(If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

12-26-84

WT

Signed Don Thompson  
(TECHNICIAN)

6139