

1051801

4-7

API NUMBER 15-067-20,769 0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SE ; SEC. 19, T 28 S, R 36
660 feet from S section 11
500 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA INC.
Name & Address: P.O. Box 26100
Oklahoma City, OK 73126-0100

Lease Name Spikes A Well # 3
County Grant
Well Total Depth 6100 198.25 ft
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1821

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____
Plugging Contractor J.W. Gibson Well Service Co. License Number 5866

Address P.O. Box 466, Ulysses, KS 67880-0466

Company to plug at: Hour: 11 a.m. Day: 7 Month: 4 Year: 19 94

Plugging proposal received from Steve Moran
(company name) OXY USA INC. (phone) 316-356-3032

logs: 5 1/2" at 6099' w/900 sx cement, PSTD 6050'. Perfs at 5301-10'
5 1/2" was cemented to surface-company had a bond log to prove it.

1st plug run tubing to 5347', pump through tubing with 60 bbl. gel followed by 40 sx cement,
2nd plug pull tubing to 1800' and spot 75 sx cement, 3rd plug pull tubing to 900' and
circulated cement to surface with 75 sx.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6 p.m. Day: 7 Month: 4 Year: 1994

ACTUAL PLUGGING REPORT 1st plug ran tubing to 5347' and pumped through tubing with 60 barrels
gel followed by 40 sx cement,

2nd plug pulled tubing to 1800' and spotted 75 sx cement,

3rd plug pulled tubing to 900' and circulated cement to surface with 75 sx.

Remarks: Used 60/40 Pozmix 6% gel by Dowell. No casing recovery.

If additional description is necessary, use BACK of this form.
observe this plugging.

INVOICED

DATE 4-28-94
INV. NO. 40356

Signed Richard W. Lepp APR 12 1994

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas