

4-071188

051-02830-00-00

RECEIVED  
KANSAS CORP COMM  
9-19  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 7-3-63

C S2 N2 /4 SEC. 09, 13 S, 19 W  
3300 feet from S section line  
2640 feet from E section line

Operator license# 5252

Lease: Johnson Well # 1

Operator: R.P. Nixon Operations, Inc.

County: Ellis

Address: 207 West 12th Street  
Hays, Kansas 67601  
Paul Nixon

Well total depth 3797 123.40 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 175 feet

Aband. oil well ☒, Gas well ☐, Input well ☐, SWD ☐, D & A ☐

Plugging contractor: Allied Cementing - Co Tools License# -

Address: Russell, Kansas 67665 - Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 19 Month: September Year: 1996

Plugging proposal received from: Paul Nixon to Herb Deines

Company: R.P. Nixon Operations, Inc. Phone: 913-628-3834

Were: 8 5/8" - 175' S.P. w/100 sxs cmt. 5 1/2" casing set at 3796' w/150 sxs cement.  
Operator said Dakota squeezed in 1981 with 175 sxs cement. Perfs. 3626' - 3453' - Elv. 2118'.  
Casing leak can get down to 1280' - casing leak 1200'. Proposal by Herb Deines.  
Run tubing to fish - spot 25 sxs cement with 2 sxs hulls. Pulled 300' tubing and circulated  
cement to the top - then squeeze 5 1/2" casing and 5 1/2" casing x 8 5/8" annulus with  
cement. Total 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 10:30 A.M., Day: 19, Month: September, Year: 1996

Actual plugging report: Nixon ordered 250 sxs 60/40 pozmix - 10% gel and 500# hulls.  
Pumped in with pump truck, spotted and displaced cement through tubing.

- 1) Ran 2 3/8" tubing to 1240' spotted and displaced w/25 sxs cement w/2 sxs hulls.
- 2) 2 3/8" tubing at 940' w/70 sxs cement w/3 sxs hulls circulated with cement.
- 3) Squeezed 5 1/2" x 8 5/8" annulus w/130 sxs cement. Max. P.S.I. 100#.
- 4) Squeezed 5 1/2" casing w/25 sxs cement. Max. P.S.I. 50# or less. Witnessed squeezes only.

Remarks: Cemented by Allied Cementing.

Condition of casing(in hole): GOOD BAD Any plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [ X ] did not [ ] observe the plugging.

(Part)

DATE 9-27-96

INV. NO. 46634

(agent)  
Form CP-2/3