

4-080211

3-11

TO:

API number 15- 051-24,948-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

SW SW SW /4 SEC: 3 - 13 - 19 W
330 Feet from S (N/S) Line
4950 Feet from E (E/W) Line

Operator License# 5252

LEASE: Kreutzer WELL # 1

Operator: R. P. Nixon Operations, Inc.

County: ELLIS 124.80

Address: 207 West 12th Street
Hays, Kansas 67601

Well total Depth 3840 feet
Conductor Pipe inch @ feet
Surface pipe 8 5/8 inch @ 207 feet

Aband. Oil Well Gas Well Input Well SWD: D & A:

Plugging contractor: Jay-Lan Corp License#: 5128

Address: 207 West 12th, Hays, KS

Company to plug at: Hour: 08:15 am Day: 11 Month: March Year: 1997

Plugging proposal received from: Paul Nixon

Company: Jay-Lan Corp Phone:

Were:
4 1/2" casing set at 3839'. PBTD 3768' with cement. Perfs from 3441'-3648'. Shoot casing below the salt section, pull to 2075' and pump 95 sx 60/40 poz, 10% gel. Pull casing to 1525' and pump 40 sx 60/40 poz, 10% gel. Pull to 750' and pump 60/40 poz, 10% gel. Pull casing to 150 feet and circulate cement. Pull casing and top off.

Plugging proposal recived by: Herb Deines

Pluggings operations attended by agent? All [], Part [], None []

Completed Hour: 05:30 pm Day: 11 Month: March Year: 1997

Actual plugging report:
Shot casing at 2005' and pulled 20' landing joint. Pumped 95 sx 60/40 poz, 10% gel and 200# hulls. Casing stuck in the hole. Tied back on to casing and pumped 180 sx 60/40 poz, 10% gel and circulated cement to surface in annulus.

05-01-97

Remarks: Elevation: 2147 GL, Anhydrite top: feet Anhy. plug: Y

Dakota plug: Y Bottom plug in place: Y

Plugged through drill pipe: T

Arbuckle top: Cemented by: Allied cementing

I did [] did NOT [] observe the plugging.

INVOICED
MAY 02 1997
DATE
INV. NO. 48052

Bruce Basye
(agent)



RECEIVED
KANSAS CORP COM
MAY 1 1997