

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-22, 573400-00

NW-NE-SE, SEC. 21, T. 13S, R. 18W

2310 FEET FROM N(S) SECTION LINE

990 FEET FROM W(E) SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 7027

LEASE NAME T. ROTH WELL # 1

OPERATOR: DAMAR OIL EXPLORATION
NAME & ADDRESS P.O. BOX 70
HAYS, KANS. 67601

COUNTY ELLIS 5 20.25

WELL TOTAL DEPTH 3700 FEET

CONDUCTOR PIPE: SIZE 0 FEET

SURFACE CASING: SIZE 8 5/8 FEET 517

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR DREILING OIL INC. LICENSE NUMBER 5145

ADDRESS RR. I VICTORIA, Mo. 67671

COMPANY TO PLUG AT: HOUR: 7:00 AM DAY: 21st MONTH: AUG. YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM PETE WALDSCHMIDT

(COMPANY NAME) DREILING OIL INC. (PHONE) 913-735-2204

WERE: 8 5/8" - 517^{ET} SP. CUL W/285ST COMMON QUICK SET (BY ALLIED)

ORDER 210ST 50ST 150 FORMIX 4% GEL-3% CA-CL AND 8 5/8" Plug

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

ARTBUCKLE @ 3686^{ET} EN 2077^{ET} ANHY 1383.

PLUGGING PROPOSAL RECEIVED BY *Pete Waldschmidt*
(TECHNICIAN) DOIC

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 1:30 AM DAY: 21st MONTH: AUG. YEAR: 19 83

ACTUAL PLUGGING REPORT

ORDERED 210ST 50ST 150 FORMIX 4% GEL-3% CA-CL. (BY ALLIED CMT.)

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 3660^{ET} W/20ST CMT, 2nd Plug @ 1410^{ET} W/20ST CMT.

3rd Plug @ 690^{ET} W/100ST CMT, 4th Plug @ 240^{ET} W/40ST CMT.

5th Plug. Solid Bridge @ 40^{ET} to 0ST W/10ST CMT, 10ST BROCKLE - 10ST HOUSEHOLE (CIRCULATE)

REMARKS: (BY ALLIED CMT)

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1983

CONSERVATION DIVISION
Wichita, Kansas

I (~~DID~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED *Pete Waldschmidt*
(TECHNICIAN) DOIC

INVOICED

DATE 8-31-83
INV. NO. 5398-L