

4 060038

11-22

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-24,623-00-00

NE SE NW, SEC. 21, T 13 S, R 18 W/EX

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Operator: Liberty Operations & Compressions

Name & Address 308 West Mill

Plainville, KS 67663

Lease Name Dreiling Well # 1

County Ellis 120.25

Well Total Depth 3700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, KS

Company to plug at: Hour: 11:30PM Day: 22 Month: November Year: 19 89

Plugging proposal received from Jack Fox

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: Space all plugs with heavy drilling mud through drill pipe.

Order 205 sxs, .60/40 6% gel 1/4# floccul per sx.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXXX

Operations Completed: Hour: 11:30PM Day: 22 Month: November Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3687' with 20 sxs. Arbuckle at 3692'

2nd plug at 1400' with 20 sxs. Anhydrite 1380-1405'

3rd plug at 675' with 100 sxs. Dakota 374-674'

4th plug at 270' with 40 sxs. Surface pipe to 218'

5th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs.

Remarks Allied cementing (If additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

DATE JAN 04 1990

INV. NO. 26866

Signed Herb Deines (TECHNICIAN)

Herb Deines