

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20897-00-00 *NO INV. WILL BE ISSUED - PLUG DT. EXCEEDS TIME LIMIT.*
Spot: W2NENE Sec/Twnshp/Rge: 3-10S-19W
4620 feet from S Section Line, 990 feet from E Section Line
Lease Name: KORTAN Well #: 1
County: ROOKS Total Vertical Depth: 3650 feet

Operator License No.: 32169
Op Name: DOPITA, DON DBA MAVERICK OIL CO.
Address: 107 W ANN ST
ZURICH, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	248	0	w/175 sxs cmt
PROD	4.5	3650	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/30/2003 3:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RON CUMMINGS Company: MAVERICK OIL CO. Phone: (785) 662-3264

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 200# hulls.
No Alt II records. Perforate Anhy 1515'. Base Dakota 950'. Base surface pipe 290'.
Top of packer cemented in hole 3100'.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 04/30/2003 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated at 1515' - 950' - 290'.
Ran tubing to 3100'. Allied pumped 45 sxs 60/40 pozmix - 10% gel with 100# hulls.
Pulled to 2100' - pumped 45 sxs cement with 100# hulls.
Pulled tubing to 1100' - pumped 50 sxs cwc. PTOH.
Hooked to 4 1/2" casing - pumped 20 sxs cement.
Max. P.S.I. 1000#. S.I.P. 1000#.
Hooked up to 8 5/8" - pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Note: Left packer and tubing in the hole 3100'.

Information received from Allied Cementing Ticket-Invoice #14757 dated 04/30/2003 - plugged per Herb Deines instructions.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN) CM

RECEIVED Form CP-2/3

JAN 20 2011

KCC WICHITA

JAN 18 2011

Jan. 10. 2011 9:32AM Allied Cementing Co. LLC NO. 3431 P. 1
ALLIED CEMENTING CO., INC. 14757

REMIT TO P.O. BOX 31
 RUSSELL, KANSAS 67665

SERVICE POINT:
Y

DATE <u>4-29-03</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START <u>3:00am</u>	JOB FINISH <u>5:00pm</u>
LEASE <u>NORTON</u>	WELL# <u>1</u>	LOCATION <u>ZURICH 1E 15</u>			COUNTY <u>ROCK</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR <u>DLIEFER</u>	OWNER
TYPE OF JOB <u>PTA</u>	
HOLE SIZE _____ TD _____	CEMENT
CASING SIZE <u>4 1/2</u> DEPTH _____	AMOUNT ORDERED <u>200 6 3/4 1090 CEL</u>
TUBING SIZE <u>2 1/2</u> DEPTH _____	<u>200# HULLS</u>
DRILL PIPE _____ DEPTH _____	<u>USFA 175 SKS</u>
TOOL _____ DEPTH _____	
PRES. MAX _____ MINIMUM _____	COMMON <u>105</u> @ <u>7.45</u> <u>750.75</u>
MEAS. LINE _____ SHOE JOINT _____	POZMIX <u>70</u> @ <u>3.82</u> <u>266.20</u>
CEMENT LEFT IN CSG. _____	GEL <u>22</u> @ <u>5.73</u> <u>125.06</u>
PERFS. _____	CHLORIDE _____ @ _____
DISPLACEMENT _____	<u>Hulls</u> <u>2</u> @ <u>18.00</u> <u>36.00</u>
EQUIPMENT	
PUMP TRUCK CEMENTER <u>MARK</u>	
# <u>345</u> HELPER <u>DAVE</u>	
BULK TRUCK	HANDLING <u>200</u> @ <u>1.15</u> <u>230.00</u>
# <u>312</u> DRIVER <u>ROGER</u>	MILEAGE <u>5.4</u> @ <u>5.56</u> <u>30.00</u>
BULK TRUCK	TOTAL <u>1752.75</u>
# _____ DRIVER _____	

REMARKS:

SERVICE

45 SKS C 3000 w/100# HULLS
45 SKS C 2100 w/100# HULLS
50 SKS C 1100 CEMENT
TREN ONTO 4 1/2 MIXED 20 SKS
PRES TO 1000"
TREN ONTO 8 3/8 MIXED 15 SKS
PRES TO 500"

DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____ 475.00
 EXTRA FOOTAGE @ _____
 MILEAGE 35 @ 3.50 122.50
 PLUG @ _____

TOTAL 547.50

CHARGE TO: C.E.C.
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

 @ _____
 @ _____
 @ _____
 @ _____
 @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____

RECEIVED
 JAN 20 2011
 KCC WICHITA