

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02110-00-00
 Spot: SESESE Sec 26 Twp 18 S Rng 22 E / W
86 Feet from N / S Line of Section
343 Feet from E / W Line of Section
 GPS: Lat: 38.447649 Long: 94.938181 Date: 3/3/10
 Lease Name: Cornett Well #: 02 (COR 02)
 County: Miami Total Vertical Depth: 415 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>State of Kansas</u>	<u>PROD - Casing</u>	<u>2.000</u>			
Address 1: <u>1500 W. Seventh</u>	<u>T1 - Tubing 1</u>	<u>0.750</u>	<u>415</u>	<u>415</u>	<u>Brass Pipe</u>
Address 2: <u>Fee Fund</u>					
City: <u>Chanute</u>					
State: <u>KS</u> Zip Code: <u>66720</u> - <u></u>					

Well Type: GAS - Natural Gas - Production UIC Docket No.: _____ Date/Time to Plug: 12/1/10 / 9:00 am
 Plug Co License No.: 33749 Plug Co. Name: Kepley Well Service, LLC
 Proposal Rcvd from: Jeff Fredricks Company Name: Kepley Well Service, LLC Phone: (620) 433-3489

Proposed
Plugging
Report:

Fill the well full of cement from bottom to top.

Plugging Proposal Received By: Taylor Herman Witness Type: ZERO - None
 Date/Time Plugging Completed: 12/1/10 / 12:00 pm KCC Agent: Taylor Herman

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Pulled 415' of 3/4" brass pipe from inside the 2" production casing. Ran 1" pipe down to 415' inside the 2" production casing. Washed 1" pipe down to 425' and hit solid on the backside of the 2" production casing. Pumped 98 sacks of cement from bottom to top on the inside and outside of the 2" production casing. Cut-off and backfilled.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Contract #EVT0000017 Control #20110001-002

Plugged Thru: TBG - Tubing **RECEIVED** Plugged Due to Compliance Issue: Yes No

District: 03 **DEC 23 2010** Taylor C. Herman
 KCC WICHITA (Technician)
 Form: District Plugging Report - _____