

6 020516

8-4

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-23906-00-00
SW SW SW, SEC. 4, T 13 S, R 19 W/Ex

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Kreutzer Well # 1

Operator: Ritchie Exp Inc.

County Ellis 122.36

Name & Address 125 N. Market Suite 1000

Well Total Depth 3765 PBD 3720 feet

Wichita, Ks. 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 219 w/175 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Same License Number _____

Address _____

Company to plug at: Hour: 9:00AM Day: 4 Month: August Year: 19 89

Plugging proposal received from Tom Post

(company name) _____ (phone) _____

were: 4 1/2" set at 3756' w/125 sks. 60/40 poz 10% salt.

Perf 3690' to 3651'. Baker port collar at 1471' w/450 sks 50/50 poz

.6% gel ewe. Ran wireline to 4038'. Shot 3 holes at 1800' and 3 holes 1015'.

Gilbert Balathazor

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00AM Day: 4 Month: August Year: 19 89

ACTUAL PLUGGING REPORT 600 lbs. press. on annulus. No cement. Pumped 50 sks of
of 60/40 poz 8% gel followed w/180 sks mix w/500 lbs hulls. Max pres 1600#. Shut in 800 #.

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1989
8-17-89

Remarks: By Allied (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-21-89

Signed Gilbert Balathazor (TECHNICIAN)

INV. NO. 25703

8-4