

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24567-00-00
Spot: NESWNE Sec/Twnshp/Rge: 21-13S-20W
3634 feet from S Section Line, 1677 feet from E Section Line
Lease Name: DREILING Well #: 1
County: ELLIS Total Vertical Depth: 3830 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 N MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	232	0	
PROD	5.5	3818	2505	

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/20/1988 8:00 AM
Plug Co. License No.: 5111 Plug Co. Name: ROCKHOLD ENGINEERING, INC.
Proposal Revd. from: JIM ROCKHOLD Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 483-3141

Proposed
Plugging
Method:

Plugging Proposal Received By: DENNIS HAMEL WitnessType: NONE
Date/Time Plugging Completed: 10/31/1988 12:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Dumped sand to 3460' and 5 sxs cement.
Shot casing at 3100' - 2900' - 2500'.
Pulled 69 joints of 5 1/2" casing.
Allied plugged well with 600# hulls and 250 sxs of 65/35 pozmix
with 10% gel and 1/4# flocele per sack.
Max. P.S.I. 100#. S.I.P. 200#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)