

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company
Complete Address P. O. Box 1201, Great Bend, Kansas 67530
Lease Name Nick Geist Well No. 1-V
Location SW NE NW Sec. 25 Twp. 13 Rge. (E) (W) 18
County Ellis Total Depth 3686'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Pipe Pulling
Address Box 176, Chase, Kansas 67524 License No. 683
Operation Completed: Hour 9:30 Day 31 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3686' 8 5/8 csg set at 252' cwc 180 sk.
5 1/2 csg set at 3688' cw 125 sk cem.
5 1/2 csg FBTD 3620 With top perf. (3366-3371)
Set 5 1/2 wood plug at 3300' -poured 20' sand -dumped 4 sk cmt W/dump bailer. (3300-3250)
Cutoff & recovered 2811' of 5 1/2 csg.
Pumped down 8 5/8 csg W/25 sk gel & water W/300 lbs hulls -released 8 5/8 plug and
pumped 125 sk 50-50 poz 6% total gel. by Allied Cementing Co. PP 450 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Mussey
Well Plugging Supervisor

DATE 9/4/74

INV. NO. 9815-W