

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22, 281-00-00 ✓

245 North Water
Wichita, KS 67202

Operator's Full Name SUNRISE DRILLING

Complete Address P.O. BOX 1114 - HAYS, KANS. 67601

Lease Name KENNEDY Well No. #1

Location NE-NE-NW Sec. 26 Twp. 13 Rge. 18 (East) (West)

County ELLIS Total Depth 3628 ^{EF} 117.91

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor MONTGOMERY DRILLING (LEROY HUNT)

Address BOX 1114 HAYS, KANS License No. _____

Operation Completed: Hour: 4:30 PM Day: 1 Month: FEB Year: 19 81

The above well was plugged as follows:

8 5/8" 250 EF SP. CUL w/ 170ST 60/40 Pozmix - 2% GEL - 3% CA-CL (2% Alumina)
ORDERED 110ST 50/50 Pozmix 6% GEL. + 8 5/8" PLUG. (ELV. 2070)
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
1ST PLUG. @ 660 EF w/ 65ST Int.
2ND PLUG. @ 240 EF w/ 30ST Int.
3RD PLUG. → SULLO BRIDGE FULL'S PLUG @ 40ST to 0 w/ 10ST Int.
5ST IN RAT HOLE.

CEMENTED BY SWD. ENT.

STAMP: CONSERVATION DIVISION
Wichita, Kansas
FEB - 3 1981

I hereby certify that the above well was plugged as herein stated.

DATE 3-13-81
INV. NO. 4952w

Signed: Maurice Shurt
Conservation Division Agent

INVOICED

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

15-051-22281-00-00

March 13, 1981

INVOICE NUMBER: 4952-W

TO: Sunrise Drilling

Box 1114

Hays, KS 67601

PLUGGING ASSESSMENT AS FOLLOWS:

Kennedy #1

NE NE NW, Sec.26-13S-18W

Ellis

Montgomery Drlg.

\$117.91

NOTE: We also need the following before our file is completed:


- Well Plugging Record (CP-4)
- Well Log
- Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



For Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, Ks 67601

is hereby assigned to supervise the plugging of the above mentioned well.