

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

15-051-20327-00-00

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bank Building Wichita, Kansas

Lease Name Orth Well No. 1

Location NW NW SE Sec. 4 Twp. 13 Rge. 19 (E) (W) X

County Ellis Total Depth 3853

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 2P Day 9 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3853' @ 5/8 csg set at 228' cwc Cmt. Mat. 100 sc 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 10/11/68

INV. NO. 8613-4