

KANSAS

af
STATE CORPORATION COMMISSION

15-051-20896-00-00

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration Company

Complete Address 416 Union Center Bldg., Wichita, Kansas

Lease Name Bemis Well No. 1

Location NE SW SE Sec. 28 Twp. 13 Rge. (E) (W) 19

County Ellis Total Depth 3502

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Hellar Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2 A Day 25 Month 11 Year 1970

The above well was plugged as follows:

RTD 3502' 8 5/8 csg set at 219' cwc Cmt. Mat. 100 sk 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Messing
Well Plugging Supervisor

INVOICED

DATE 12/1/70
INV. NO. 2960-W