

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
OCT 31 1975
10-31-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name H. A. Chapman 15-051-21017-00-00

Complete Address Box 65, Great Bend, Kansas 67530

Lease Name Pete Sack Well No. 1

Location NE NW NW Sec. 25 Twp. 13 Rge. (E) (W) 19

County Ellis Total Depth 3700'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 2:30 PM Day 28 Month 10 Year 1975

The above well was plugged as follows:

Total Depth 3700' 8 5/8 csg set 363' cwc 200 sk.

4 1/2 csg set 3698' cw 225 sk cem.

4 1/2 csg PFS (3645'-3658') (3372'-3366') (3344'-3340') (3256'-3253')

Set castiron BP (3450') (3300') (3230') Dumped 3 sk cem W/dump bailer (3230-3200)

Cutoff & recovered 2830' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls- released

8 5/8 plug & 140 sk "Halco-Light" cement by Hallib. Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Mersing
Well Plugging Supervisor

DATE 10/31/75

INV. NO. 2158-W