

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-173-01.025 0001

LEASE NAME Hay

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1 OWTO

4290' Ft. from S Section Line

3630' Ft. from E Section Line

SEC. 36 TWP. 28 RGE. 1W (E) or (W)

COUNTY Sedgwick

Date Well Completed 01-10-90

Plugging Commenced 01-10-90

Plugging Completed 01-10-90

LEASE OPERATOR Jay Boy Oil, Inc.

ADDRESS 224 E. Douglas #425 Wichita, Ks 67202

PHONE#(316) 264-3700 OPERATORS LICENSE NO. 4569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01-10-90 (date)

by Steve Van Giesun (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation D & A Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	old hole					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

50 sks @ 3639' Steve Van Giesun on location

235 sks 375' to surface 300 sks total - common

15 sks in rathole Haliburton tkt # 890863

Plug down @ 8pm

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allen Drilling Co. License No. 5418

Address 1105 Walnut Box 1389 Great Bend, Ks 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jay Boy Oil, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jay Ablah - President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jay Ablah

(Address) 224 E. Douglas #425 Wichita, Ks

BETTY B. HERRING
NOTARY PUBLIC SUBSCRIBED AND SWORN TO before me this 5th day of February, 19 90
STATE OF KANSAS
My Appt. Exp. 10-07-93

Betty B. Herring Notary Public

My Commission Expires: 10-07-93

Memorandum

15-173-D1025-0001

RE: Jay Boy Oil Company

Plugging Procedures
Hay #1 - SW NE NW 36-28-1W
Sedgwick County, Kansas

After logging was completed on the well, the drill pipe was run back into the hole, open ended to 3639'. At 3639' the well bore was reconditioned by circulating drilling mud for approximately two hours.

Halliburton Cementing Company arrived on location at approximately 1100 hours and plugging operations began.

A 50 sack cement plug was spotted at 3639', to isolate both the Simpson and Maquokta formations. The cement plug was displaced with drilling mud for a balanced plug.

The drill pipe was pulled to 375' for the top plug. At 375', cementing operations began by circulating cement back to surface. At 1500 hours, Halliburton had pumped 150 sacks of cement, with no cement returns to surface. An additional 100 sacks of cement was ordered to complete plugging operations.

After a waiting period of two hours, a wire line was run into the well bore to find the top of the cement. The cement was found at 155'. The drill pipe was run back into the well bore to circulate cement back to surface. An additional 80 sacks of cement was needed to bring cement returns to surface. The drill pipe was pulled from the well bore and topped off with five sacks of cement.

The rat hole was plugged by pumping 15 sacks of cement through a joint of drill pipe and circulated back to within 3 feet of surface.

The plugging operation was completed on 1/10/90 at 1915 hours.

Drilling mud weight 9.5#/gal.
Drilling mud viscosity, 48.

Hay #1 OWWO
SW NE NW 36-28-1W
Sedgwick County

WASHDOWN REPORT

0' - 20' - Very hard cement & wood pieces
20' - 170' - Drilling mud
170' - 185' - Very thick, unset cement
185' - 3300' - Drill mud

Rec'd
MAILED

JAN 17 1990

CONSERVATION DIVISION
WICHITA, KANSAS

Steve Van Gieson

Steve Van Gieson
1-11-90