

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County. Sec. 34 Twp. 11S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Earl F. Wakefield

Lease Name Dreiling Well No. 4

Office Address 515 Union Center Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed October 31 19 51

Application for plugging filed January 18 19 62

Application for plugging approved 19

Plugging commenced December 5 19 61

Plugging completed December 5 19 61

Reason for abandonment of well or producing formation Non Economical

If a producing well is abandoned, date of last production November 20 19 61

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3498 Bottom 3517 Total Depth of Well 3517 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT	
				8 5/8"	134	5'	
				5 1/2"	3512	5'	
		5 1/2" Cemented with 200 sacks at Bottom DV Tool at 1216' cement to surface with 500 sacks					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halco D.M. Plug at 3402 Dumped five sacks cement
Bridge at 900 feet Dumped 20 sacks cement
Cut off 5 1/2" and 8 5/8" five feet below ground level
welded on cap

RECEIVED
JAN 25 1962
01-25-62
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Brister Drilling Company, Inc.

Address Box 485, Plainville, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
EARL F. WAKEFIELD (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Building
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 62

Wanda M. Kiley
Notary Public.

My commission expires January 25, 1965



Drilling #4
 Owner: Karl F. Wakefield
 Contractor: Karl F. Wakefield
 Comm: 10-21-51 Comp: 10-31-51

NW NE NE 34-11-17W
 Ellis County, Kansas
 Casing: 134.40' of 8 5/8"
 2526.70' of 5 1/2"

Elevation 1999

Surface	138
Shale & Shells	614
Sand	655
Shale & Shells	750
Sand	849
Shale & Red Bed	1167
Shale	1193
Anhydrite	1238
Shale-Lime Streaks	1350
Shale & Shells	1940
Shale & Lime Streaks	2070
Lime & Shale	2615
Shale & Lime	2745
Lime & Shale	2845
Shale & Lime	2940
Lime & Shale	3230
K. G. Lime	3412
Lime & Shale	3440
Lime	3495
Arbuckle Lime	3517
Total Depth	3517

COMMISSION
 01-25-62
 DIVISION

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the Drilling #4 well located NW NE NE 34-11-17W, Ellis County, Kansas.

Karl F. Wakefield

Subscribed and sworn to before me this 14th day of November, 1951.

[Signature]

My Commission Expires: 12-23-54

COMMISSION
 01-25-62
 DIVISION