

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

15-173-01025-10000

NORTH

Locate well correctly on above
Section Plat

Sedgwick County. Sec. 36 Twp. 28 Rge. 1 (E) (W)
Location as "NE/CNWxSWx" or footage from lines SW NE NW
Lease Owner Shawver-Armour, Inc.
Lease Name Hay Well No. 3
Office Address
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-17-56 19
Application for plugging filed 2-17-56 19
Application for plugging approved 2-17-56 19
Plugging commenced 2-17-56 19
Plugging completed 2-17-56 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Mississippian Depth to top 3214 Bottom 3300 Total Depth of Well 3300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	194	8-5/8	194	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3300 - 180 Fill w/ heavy mud
180 Good permanent plug and 15 sx cement thru drill pipe
30' Fill w/ heavy mud. Then set #2 plug - good permanent plug
and 10 sax cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) James Armour James Armour
817 Central Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22 day of February, 19 56

My commission expires Dec. 29, 1959

Marjorie Hall

Notary Public.



02-23-56

DRILLING LOG

COMPANY: Shawver-Armour, Inc.
CONTRACTOR: Shawver-Armour, Inc.

Location: SW 1/4 NW 36-28-14
Bedgrick

WELL NAME: MAY #3

Elevation: 1301 KB

DATE LOGGED: February 9, 1956
COMPLETED: February 17, 1956

DRILLING RECORD

8-1/8 198' 175 sq. cm.

FORMATION	FROM	TO	
Surface Clay & Sand		60	
Sand & Gravel		100	
Clay, Shale w/shells		167	
Anhydrite		195	
Anhydrite w/shale & shells		275	
Shale & Lime		460	TOPS
Lime & Shale		515	
Shale w/lime shells		960	Kansas City 2724
Shale & Lime Strata		1365	Mississippi Chert 3240
Shale & Shells		1500	Mississippi Beds 3256
Lime & Shale		2105	RTD 3300
Shale		2301	
Stalactite sand & shale		2501	
Lime & Shale		2603	
Shale & Lime Shells		2715	
Lime		2780	
Lime		2900	
Lime w/shale		3095	
Shale w/lime		3115	
Lime & Shale		3215	
Lime		3300	

STATE OF KANSAS)
) ss
BEDGRICK COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

By James Armour
James Armour, Sec. Treas.

Subscribed and sworn to before me this 22 day of February 1956.

Marjorie Hall
Notary Public - Marjorie Hall

My commission expires December 9, 1957

