

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-249830000

LEASE NAME Slaughter

WELL NUMBER 1

330 Ft. from N Section Line

990 Ft. from E Section Line

SEC. 5 TWP. 13 RGE. 19 (S) or (W)

COUNTY Ellis

Date Well Completed 6-8-98

Plugging Commenced 6-8-98

Plugging Completed 6-8-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

06-17-1998

LEASE OPERATOR Lotus Operating Co., L.L.C.

ADDRESS 107 N. Market, Suite 416, Wichita, KS.

PHONE(S) (316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-8-98 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	226'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each so
Push bridge plug to 3,850', pump 25 sax cement on plug. Push plug to 1,500', pump 25 sax cement on plug. Push plug to 760', pump 100 sax cement on plug. Push plug to 270', pump 40 sax cement on plug. Push wiper plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. 60/40 pozmis, 6% gel, 4# floseal/sack

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., PO Box 709, Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lotus Operating Co., L.L.C.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed thereon, the same are true and correct, so help me God.

Contractor
(Employee of ~~Operator~~ or ~~Operator~~)
SHEILDS DRILLING CO.
(Signature) Jack P. Beeman
Shields Bldg.
(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 98

Lucretia Phillips
Notary Public

My Commission Expires: _____





Shields


15-051-24983-00-00

Russell, Kansas

WELL LOG

Operator: Lotus Operating Co., L.L.C.
 Well: Slaughter #1
 Commenced: May 29, 1998
 Completed: June 8, 1998
 Contractor: Shields Drilling Co.

Well Description: NW NE NE
 Sec. 5-13S-19W
 Ellis Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	226'	Cmtd. w/140 sax

Elevation: 2,167' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Rock & shale	229'	
Sand & shale	1,501'	
Anhydrite	1,545'	
Shale & sand	1,658'	
Shale	2,972'	
Shale & lime	3,410'	
Lime	3,900'	RTD