


15-051-21089-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County, Sec. 5 Twp. 13 Rge. 19W (E) (W)
Location as "NE/CNW&SW" or footage from lines NW SE SE
Lease Owner F & M OIL CO., INC.
Lease Name WANNAMAHER Well No. 1
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 28 19 75
Application for plugging filed September 28 19 75
Application for plugging approved September 28 19 75
Plugging commenced September 28 19 75
Plugging completed September 28 19 75
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3870 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug @ 550' w/70 sacks 50/50 Pozmix, 2% Gel.
Middle plug @ 185' w/20 sacks 50/50 Pozmix, 2% Gel
Top plug @ 40' w/1/2 sack hulls and 10 sacks cement. (50/50 Pozmix, 2% Gel)

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1975
10-01-1975
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke Drilling Co.
Address Box 823, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON
Wayne Dobbs

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs
Box 823, Great Bend, Kansas (Address)

Subscribed and Sworn to before me this 29th day of September 19 75

My commission expires April 11, 1978
Notary Public.

15-051-21089-0000

DRILLERS' WELL LOG

DATE COMMENCED: September 22, 1975
DATE COMPLETED: September 28, 1975

F & M Oil Co.
MAKINAKER # 1
NW SE SE
Sec. 5-T13-R19W
Ellis County, Kansas
ELEVATION: 2179 K.B.

0 - 60' Post Rock
60 - 930' Shale and Shells
930 - 1200' Shale w/Sand Streaks
1200 - 1480' Red Bed
1480 - 1542' Anhydrite
1542 - 2085' Shale and Shells
2085 - 3509' Shale and Lime
3509 - 3842' Lime and Shale
3842 - 3870' Dolomite
3870' RTD

FORMATION TOPS

Anhydrite 1520
Lensing 3509
Artuckle 3842
RTD 3870

SURFACE PIPE: Set 203' of
8 3/8", 26# used pipe w/125 sacks
Common, 2 1/2 Gal, 3 1/2 cu.

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Wayne Hobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Hobbs

Subscribed and sworn to before me this 30th day of September, 1975.

Wendy M. Hague
Notary Public

My Commission Expires: April 11, 1978

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1975
10-01-1975
CONSERVATION DIVISION
Wichita, Kansas