

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

15-051-30249-00-00  
WELL PLUGGING RECORD

Ellis County, Sec. 3 Twp. 13S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW SW

Lease Owner Okmar Oil Company

Lease Name Kreutzer Well No. 1

Office Address 1130 Wichita Plaza, Wichita 2, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-4-66 19

Application for plugging filed 3-4-66 19

Application for plugging approved 3-4-66 19


Plugging commenced 3-4-66 19

Plugging completed 3-4-66 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, Victoria, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3777 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 196'   | none       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set Plug @ 540' with 20 sacks cement  
Set Plug @ 180' with 20 sacks cement  
Bridged Plug @ 40' with 1/2 sack hulls and 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

MAR 10 1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1966

My commission expires April 1, 1967

Ulanda Nichols  
Notary Public.

15:05:30249:00:00  
DRILLER'S LOG

COMPANY: Okmar Oil Company  
CONTRACTOR: LEBEN DRILLING, INC.  
FARM: KREUTZER #1  
LOCATION: SW NW SW Sec. 3-13S-19W  
ELLIS COUNTY, KANSAS  
COMMENCED: 2-24-66  
COMPLETED: 3-4-66

|      |             |                          |
|------|-------------|--------------------------|
| 0    | 40          | Surface clay, sand       |
| 40   | 196         | Blue Shale               |
| 196  | 900         | Shale                    |
| 900  | 1100        | Sand                     |
| 1100 | 1415        | Redbed                   |
| 1415 | 1459        | Anhydrite                |
| 1459 | 2010        | Shale, Shells            |
| 2010 | 2465        | Lime, Shale              |
| 2465 | 2670        | Shale                    |
| 2670 | 3015        | Shale, Lime              |
| 3015 | 3115        | Lime, Shale              |
| 3115 | 3777        | Lime                     |
|      | <u>3777</u> | <u>RTD - D. &amp; A.</u> |

RECORDED  
MAR 10 1966

Set 8 5/8" used surface casing @ 150 sacks Sunset cement @ 196'

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Kreutzer #1 well, located SW NW SW of Section 3, Township 13 South, Range 19 West, Ellis County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS )  
                  ) SS  
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 8th day of March, 1966.

Ulanda Nichols  
Ulanda Nichols

My Commission Expires:  
April 1, 1967