

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-051-24,201-00-00

LEASE NAME Lonnon

WELL NUMBER 1

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 8 TWP. 13 RGE. 19 (X) or (W)

COUNTY Ellis

Date Well Completed 4-5-85

Plugging Commenced 4-5-85

Plugging Completed 4-5-85

LEASE OPERATOR H K & W Oil Operators, Inc.

ADDRESS P.O. Box 1851 Salina, KS 67401

PHONE#( 316 793-7327 OPERATORS LICENSE NO. 6280

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.  
 to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3751

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Bottom Plug: @ 1420' w/20 sacks cement thru drill pipe

Next Plug: @ 685' w/100 sacks " " " "

Top Plug: @ 40' w/1 sack hulls and 10 sacks cement  
 10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss. APR 11 1985  
 STATE CORPORATION COMMISSION

Leonard Williamson

(Employee of Operator    or    of

above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 9<sup>th</sup> day of April, 19 85

Dorothy M Hague  
 Notary Public

My Commission Expires: 4-29-86



15-051-24201-00-00

DRILLER'S WELL LOG

DATE COMMENCED: March 29, 1985  
DATE COMPLETED: April 5, 1985

H K & W Oil Operators, Inc.  
LONNON #1  
SW SE SW  
Sec. 8, T13S, R19W  
Ellis County, Ks.

ELEVATION: 2085 K.B.

FORMATION DATA

0 - 1160'	Surface Soil, Shale, Sand
1160 - 1414'	Shale, Shells, Red Bed
1414 - 1462'	Anhydrite
1462 - 3101'	Shale & Lime
3101 - 3126'	Shale & Sand
3126 - 3377'	Lime
3377 - 3421'	Shale & Lime
3421 - 3667'	Lime
3667 - 3751'	Shale, Lime, Chert, Sand
3751'	RTD

Anhydrite	1414'
Severy	3101'
Topeka	3126'
Heebner	3377'
Toronto	3399'
Kansas City	3421'
Base K.C.	3667'
Marmaton	3703'
Conglomerate	3732'
RTD	3751'

Surface Pipe: Set new  
8-5/8", 24# pipe @520' w/225  
sacks cement, 50/50 pozmix  
2% gel 3% cc.

A F F I D A V I T


STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 9<sup>th</sup> day of April 1985.

My Comm. Expires:



RECEIVED  
STATE CORPORATION COMMISSION

*Dorothy M. Hague*  
Notary Public

APR 11 1985  
04-11-1985  
CONSERVATION DIVISION  
Wichita, Kansas