

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-24,613-00-00

LEASE NAME Amrein

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

660 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 6 TWP. 13 SRGE. 19 (W)

COUNTY Ellis

LEASE OPERATOR Petroleum, Inc.

ADDRESS 301 N. Main, Suite 900, Wichita, KS 67202-1508

PHONE# (316) 291-8281 OPERATORS LICENSE NO. 5238

Date Well Completed 10-16-89

Character of Well D&A

Plugging Commenced 10-17-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-17-89

The plugging proposal was approved on 10-17-89 (date)

by State Plugger, Herb Dines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3930'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set. Circulate heavy mud in hole. 1st plug from 3875' to 3795' w/20 sx. 2nd plug from 1540' to 1460' w/20 sx. 3rd plug from 770' to 370' w/100 sx. 4th plug from 300' to 140' w/40 sx. 5th plug from 40' SB to Surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 2 sx Flocel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

OCT 24 1989  
10-24-1989  
CONSERVATION DIVISION  
Wichita, Kansas

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 1989

Sharan J. Branstetter Notary Public

My Commission Expires: May 18, 1993

