

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051 23,451-00-00
 LEASE NAME Armbruster

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
4,950 Ft. from S Section Line
4,950 Ft. from E Section Line

LEASE OPERATOR Walters & Walters

SEC. 12 TWP. 13 RGE. 20 ~~(E)~~ or (W)

ADDRESS 5924 Royal Lane #155, Dallas, Tex 75230 COUNTY Ellis

PHONE#(214) 363-5997 OPERATORS LICENSE NO. 6148 ⁷⁵²³⁰ Date Well Completed 7-20-83

Character of Well D & A Plugging Commenced 3-29-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 4-09-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation L-KC Depth to Top 3400 Bottom 3660 T.D. 3791

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC Perfs	Treated w/acid	0	208	8-5/8"	208	0
3595-3600	Non-Commercial	0	3790	5-1/2"	3790	2,400
3603-3605	Oil					
3614-3618						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Baker Wireline plug set at 3730. 50 sks. Class A cement spotted thru tubing on bottom. Casing shot off at 2400'. Pulled casing, cemented down 8-5/8" with 165 sks. 50-50 poz. 3% cacl chloride, 6% Gel and 5 sks cottonseed hulls. Cement fell 121 ft. Dropped 1.5 cu. yds. redy mix in top.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Sun Cementing License No.

Address P O Box 169, Great Bend, Ks. 67530

STATE OF TEXAS COUNTY OF DALLAS, ss.

Michael C. Walters

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

STATE CORPORATION COMMISSION

(Signature) Michael C. Walters

(Address) 5924 Royal Lane #155
Dallas, TEX 75230


SUBSCRIBED AND SWORN TO before me this 29 day of August, 19 85
 CONSERVATION DIVISION
 Wichita, Kansas

Susan Lynn Wilkerson
 Notary Public

My Commission Expires: June 15, 1989



SUSAN LYNN WILKERSON
 Notary Public, State of Texas
 My Commission Expires June 15, 1989 CP-4
 208-84



RECEIVED

AUG 30 1985
 08-30-1985