

15-051-19190-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 12 Twp. 13S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SW/4 NE/4  
Lease Owner Birmingham-Bartlett Drilling Co.  
Lease Name JACQUES Well No. 1  
Office Address 300 Kaufman Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 2, 19 65  
Application for plugging filed (verbal) November 2, 19 65  
Application for plugging approved (verbal) November 2, 19 65  
Plugging commenced November 2, 19 65  
Plugging completed November 2, 19 65  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Lieker  
Producing formation Depth to top Bottom Total Depth of Well 3480 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	259'	8-5/8"	259'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 540' with 20 sacks cement mixed and poured through pipe.  
Middle plug set at 250' with 20 sacks cement mixed and poured through pipe.  
Top plug set at 40' with 8 sacks cement. To surface with cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 5 1965  
11-05-1965  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Birmingham-Bartlett Drilling Co.  
Address 300 Kaufman Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF Sedgwick  
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., owner, operator, & contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM BARTLETT DRILLING CO.

(Signature) By Richard Hindery Partner  
300 Kaufman Building, Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN to before me this 4th day of November, 19 65.  
Beverly Larson  
Beverly Larson Notary Public.  
My commission expires October 2, 1966.



15-051-19190-00-00

JACQUES NO. 1 WELL

LOCATION: SE/4 SW/4 NE/4  
Section 12-13S-20W  
Ellis County, Kansas

SPUDED: 10-27-65  
DRILLING  
COMPLETED: 11- 2-65

OWNER, OPERATOR,  
and CONTRACTOR: Birmingham-Bartlett Drilling Co.  
300 Kaufman Building  
Wichita, Kansas 67202

SURFACE CASING: 8-5/8" cemented at 259'  
with 175 sacks cement.

OIL STRING: None set. Plugged 11-3-65.  
D & A.

L O G

(Figures indicate bottom of formation)

0 -	60	Shale and clay
	75	Shale and gravel
	175	Shale and shells
	210	Sandy shale
	630	Shale
	690	Sand and shale
	730	Shale and lime
	760	Pyrite
	900	Shale and shells
	1135	Sand
	1380	Red bed and shale
	1440	Red bed
	1483	Anhydrite
	2085	Shale and shells
	3158	Lime and shale
	3480	Lime
	3480	Rotary Total Depth Dry and Abandoned

11-05-1965

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the JACQUES NO. 1 WELL as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery  
Richard Hindery, Partner

Subscribed and sworn to before me  
this 4th day of November, 1965.

Beverly Larson  
Beverly Larson, Notary Public

My commission expires October 2, 1966.