


STATE OF KANSAS
STATE CORPORATION COMMISSION

15:05:2137:00:00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 22 Twp. 13 Rge. 18 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SW NE

Lease Owner R. P. Nixon
Lease Name M. Brown #3 Well No. _____
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed 19 _____
Application for plugging filed 19 _____
Application for plugging approved 19 _____
Plugging commenced 11/19/77 19 _____
Plugging completed 11/23/77 19 _____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production. 19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3700
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	590	none
				1 1/2"	3684	3027'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pushed wood plug to 3315', sanded to 3250' and ran 3 sacks cement. Loaded hole
with salt water, shot pipe at 3015', pulled 83 joints. Plugged well with 15 sacks gel,
plug and 70 sacks cement, 8 sacks gel and 30 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KESLO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 77

My commission expires _____



RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1977

CONSERVATION DIVISION
Wichita, Kansas

Well Log: M. Braun #3 NW SW NE of Sec.22, T13S-R18W, Ellis Co.,
Kansas

0' to 190' Top soil - shale
190' to 603' Shale - shells
603' - 1095' Shale - sand - redbed
1095' - 1342' Shale
1342' - 1390' Anhydrite
1390' - 1605' Redbed & shale
1605' - 1980' Shale
1980' - 2290' Lime w/shale
2290' - 2425' Shale & lime
2425' - 2625' Lime & shale
2625' - 2775' Lime with shale
2775' - 2985' Lime & shale
2985' - 3155' Lime & shale
3155' - 3222' Lime & shale
3222' - 3315' Lime
3315' - 3432' Lime
3432' - 3491' Lime
3491' - 3506' Lime
3506' - 3610' Lime
3610' - 3685' Lime
3685' Rotary total depth

15.051.21312.00.00

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1977

CONSERVATION DIVISION
Wichita, Kansas