

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD 15-0512191100-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 22 Twp. 13 Rge. 18 XE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 820' FSL
780' FWL NW/4


Lease Owner J. B. Collins
Lease Name Gross Well No. 1
Office Address 1007 Cody, Suite A. Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed 2-13 1980
Application for plugging filed 10-22 1980
Application for plugging approved 10-24 1980
Plugging commenced 12-6 1980
Plugging completed 12-6 1980

Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 3660
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

8 7/8" 1260' SS. CMC. w/ 250' 60/40 POZMIX - 2% GEL. - 3% CA-CL.
5 1/2" SET AT. 2659' w/ 100' SS. CMC. - PERF'S 2621' to 3240'
BOTTOM SANDED TO 3300' AND w/ 5' SS. CMC. SHOT PIPE @ 2525' RE. 2525'
ORDERED - 100' 50/50 POZMIX 6% GEL. -> 8' GEL. -> 2' HALL'S AND 8 7/8" P.W.G.
PUMPED IN WITH PUMP TRUCK.
PUMPED IN 8 7/8" - 1' HALL'S -> 8' GEL. - 1' HALL'S -> 100' CMC.
RELEASED PLUG. AND DISPLACED PLUG. AT 600' MAX. PRESSURE 1600 LBS
SHOT IN PRESSURE. 800 LBS WELL WILL BE UTILIZED AS WATER WELL.
BY OWNER.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc., Box 31, Russell, Kansas

STATE OF KANSAS COUNTY OF ELLIS, ss.
John B. Collins (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


1007 Cody, Suite A. Hays, Kansas 67601
(Address)

FILED 02-23-81
CONSERVATION DIVISION
WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 81

Grella P. Mizell
Notary Public.

My commission expires



DRILLING OIL, INC.

Victoria, Kansas 67671

WELL LOG

J.B. Collins
1007 Cody - Suite A
Hays, KS 67601

Company
Farm
Total Depth
Comm.
Contractor

No. 1
Gross
3,660'
1-6-80
Dreiling Oil, Inc.
Rt. #1
Victoria, KS 67671

Sec. 22 Twp. 13 Rng. 18
Location 820' FSL - 780' FWL of NR/4
County Ellis
Elevation: 2084 K. B.
2081 D. F.
2079 G. R.

Casing Record

1,360' - 8 5/8"
3,659' - 5 1/2"

Cement Record

250 sacks cement
cemented w/150 sacks common

Production:

15-051-21911-00-00

Figures Indicate Bottom of Formations

0'	65'	Post Rock
65'	612'	Shale
612'	813'	Shale
813'	960'	Sand
960'	1165'	Red Bed
1165'	1349'	Red Bed & Shale
1349'	1394'	Anhydrite
1394'	2182'	Shale
2182'	2539'	Shale & Lime
2539'	2800'	Lime & Shale
2800'	3660'	Lime & Arbuckle
3660'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Gross #1.


JOSEPH A. HESS

Subscribed and sworn to before me this 18th day of February, 1980.


Cecilia Basgall Notary Public

CECILIA BASGALL
NOTARY PUBLIC
Ellis County, Kansas

My appointment expires; November 17, 1980.

RECEIVED
STATE CORPORATION COMMISSION

OCT 24 1980
10-24-80
CONSERVATION DIVISION
Wichita, Kansas