

WELL PLUGGING RECORD

15-051-23411-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Ellis SEC. 22 TWP. 13 RGE. 18W ~~XXX~~
 Location as in quarters or footage from lines:
 SW SE NE

			*

Lease Owner Energy Reserves Group, Inc.
 Lease Name Braun 'D' Well No. 1
 Office Address 925 Patton Road, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 5/24/83
 Application for plugging filed 5/24/83
 Plugging commenced 5/24/83
 Plugging completed 5/24/83 6:30 a.m.
 Reason for abandonment of well or producing formation Non-Commercial

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3715

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surf. Casing	0	550	8-5/8"	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

1st plug @ 3680 wjth 25 sacks 50/50 Poz, 4% gel, 3% CC
 2nd plug @ 1396' with 25 sacks 50/50 Poz, 4% gel, 3% CC
 3rd plug @ 700' with 90 sacks 50/50 Poz, 4% gel, 3% CC
 4th plug @ 225' with 40 sacks, 50/50 Poz, 4% gel, 3% CC
 Bridge plug @ 40' with 10 sacks
 10 sacks in rathole
 Job complete 6:30 a.m. 5/24/83


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Barton, ss.

Jim W. Sullivan (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Jim W. Sullivan
925 Patton Rd., Great Bend, KS 67530
 (Address)



SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 83

Ronald E. Rowe
 Notary Public

My Commission expires My Appointment Expires Sept. 9, 1983

RECEIVED
 STATE CORPORATION COMMISSION

JUN 24 1983

Conservation Division
 Wichita, Kansas