

15-051-20169-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1967
12-13-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Dom E. Pratt
Complete Address: Drawer 370 Hays, Ks.
Lease Name Befort "A" Well No. 1
Location SE SE NW Sec. 23 Twp. 13 Rge. 19 (E) (W) X
County Ellis Total Depth 3706
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: L. J. Dreiling & Sons, Inc.
Address: Victoria, Ks. License No.
Operation Completed: Hour 12:45 P Day 12 Month 12 Year 1967

The Above well was plugged as follows:

RTD 3706' 8 5/8 csg set at 150' cwc 100 sc.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 100 sc cem.
thru drill pipe; Heavy mud to 150' set cementing plug and displaced 25 sc cement thru ~~drill~~
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/13/67
INV. NO. 6904-W

Signed: Geo J. Mussey
Well Plugging Supervisor