

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 106-62

LOCATION NW SW NE

SEC. 21 TWP. 11 RGE. 17W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease F.A. Bemis AUB KC

Operator Phillips Pet Co Address Box 779 Great Bend, Kans

Field _____ County Ellis

Total Depth 3389 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

16" at 62' circulated with cement - 10 3/4" at ~~xxx~~ 1074' circulate d
with 325 sax cement - 7" at 3354' with 200 sax cement behind.

Filled with sand to 3340', set 5 sax cement with dump bailer,

pulled 2395' 7" casing - pumped hole with mud to 300' (32 sax
gel) set rock bridge and 30 sax cement at 300' - heavy mud to 50',

set rock and 20 sax cement to bottom cellar.

District Conservation Agent

Date 11-8-56 RECEIVED STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 21 T. 11 R. 17W
BOOK PAGE 106 LINE 62

NOV 13 1956
11-13-56
CONSERVATION DIVISION
Wichita, Kansas