

15-051-03341-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 26-36
LOCATION NE SE SE
SEC. 21 TWP. 11 RGE. 17

Dry Hole Abandoned Oil Well x Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 3 Lease Bemis

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 3427 Feet.

(Describe briefly the manner in which the well was plugged)

15" at 120' circulated with cement - 10" at 1114' circulated
with cement - 7" at 3404' with 150 sax cement behind.
Filled with sand to 3400' set 5 sax cement with dump bailer,
pulled 1700' 7", filled hole with heavy mud to 250', set rock
bridge and 15 sax cement, filled with mud to 40', set rock
bridge and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 - 1950

CONSERVATION DIVISION

[Signature]
District Conservation Agent

Date 10-4-50

PLUGGING
FILE SEC 21 - T 11 - R 17W
BOOK PAGE 26 - LINE 36

RWD
10-06-50